SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
137	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Ground Floor	Sqm	5.63	516.00	Rs Five hundred Sixteen only
138	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. First Floor	Sqm	10.22	522.00	Rs Five hundred twenty two only
139	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Second Floor	Sqm	10.22	528.00	Rs Five hundred twenty Eight only
140	Providing and laying in Mat for RCC roof at below the steel for avoiding concrete cement slurry as per the requirement of Engineer incharge.	Sqm	211.14	73.00	Rs Seventy three only
141	Providing and removing Centering, shuttering, strutting, propping etc.,and removal of from work for vertical surface such as walls at any thickness including attched plasters, butresses, plinth cills and string courses cost of all materials, labour complete as per specification	Sqm	34.32	337.00	Rs Three hundred thirty Seven only
142	Providing and removing centering, shuttering, strutting,propping etc., for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per specifications. Ground Floor	Sqm	5.09	312.00	Rs Three hundred twelve only
143	Providing and removing centering, shuttering, strutting,propping etc., for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per specifications. First Floor	Sqm	5.09	318.00	Rs Three hundred Eighteen only
144	Providing and removing centering, shuttering, strutting,propping etc., for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per specifications. Second Floor	Sqm	5.09	324.00	Rs Three hundred twenty four only.

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
145	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. Ground Floor	MT	4.83	65188.00	Rs Sixty five thousand one hundred Eighty Eight only
146	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. First Floor	MT	2.53	65716.00	Rs Sixty five thousand Seven hundred Sixteen only
147	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. Second Floor	MT	2.64	66244.00	Rs Sixty Six thousand two hundred fifty four only.
148	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Ground Floor	Sqm	52.38	1119.00	Rs one thousand one hundred Nineteen only
149	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. First Floor	Sqm	85.54	1155.00	Rs one thousand one hundred fifty five only
150	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Second Floor	Sqm	85.54	1190.00	Rs one thousand one hundred Ninety only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
151	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Ground Floor	Sqm	26.23	816.00	Rs Eight hundred Sixteen only
152	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. First Floor	Sqm	48.81	852.00	Rs Eight hundred fifty two only
153	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Second Floor	Sqm	48.81	888.00	Rs Eight hundred Eighty eight only
154	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification.	Sqm	126.75	246.00	Rs Two hundred forty Six only
155	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside. Ground Floor	Sqm	114.14	278.00	Rs Two hundred Seventy Eight only
156	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside.First Floor	Sqm	200.40	284.00	Rs Two hundred Eighty four only .

Signature of the Contractor

Executive Engineer (Project) 17/1-

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
157	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside.Second Floor	Sqm	200.40	290.00	Rs Two hundred Ninety only.
158	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. Ground Floor	Sqm	59.64	249.00	Rs Two hundred forty nine only
159	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering. First Floor	Sqm	99.58	261.00	Rs Two hundred Sixty one only
160	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. Second Floor	Sqm	99.58	273.00	Rs Two hundred Seventy three only
161	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick. Ground Floor	Sqm	49.00	1334.00	Rs one thousand three hundred thirty four only
162	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick.First Floor	Sqm	49.00	1336.00	Rs one thousand three hundred thirty Six only
163	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick.Second Floor	Sqm	49.00	1337.00	Rs one thousand three hundred thirty Seven only

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
164	Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. Ground Floor	Sqm	65.02	1162.00	Rs one thousand one hundred Sixty two only
165	Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. First Floor	Sqm	70.73	1164.00	Rs one thousand one hundred Sixty four only
166	Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. Second Floor	Sqm	70.73	1165.00	Rs one thousand one hundred Sixty five only
167	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Ground Floor	Sqm	75.92	1362.00	Rs one thousand three hundred Sixty two only
168	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. First Floor	Sqm	75.92	1364.00	Rs one thousand three hundred Sixty four only
169	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Second Floor	Sqm	75.92	1366.00	Rs one thousand three hundred Sixty Six only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
170	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications	Sqm	641.70	64.00	Rs Sixty four only
171	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer)	Sqm	514.95	101.00	Rs one Hundred one only
172	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer)	Sqm	130.69	106.00	Rs one Hundred Six only
173	Providing ACE paint to external walls of approved colour and shade over prime's coat.after brooming & cleaning the surface and applying two coats of ACE paint with cost of all material,labour,lead lift with loading unloading etc.complete as per direction of Engineer in charge of work.	Sqm	258.80	202.00	Rs Two Hundred two only
174	Fixing of door frames in an exisying opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications.	Sqm	15.00	1202.00	Rs Two thousand two Hundred two only
175	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.62	121793.00	Rs one Lakh twenty one thousand Seven Hundred ninety three only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
176	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. Ground Floor	Sqm	8.19	5368.00	Rs Five thousand three hundred Sixty eight only
177	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. First Floor	Sqm.	8.82	5372.00	Rs Five thousand three hundred Seventy two only
178	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. Second Floor	Sqm	8.82	5376.00	Rs Five thousand three hundred Seventy Six only
179	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications.	Sqm	58.12	96.00	Rs Ninety Six only
180	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Ground Floor	Kgs	158.76	101.00	Rs one hundred one only
181	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. First Floor	Kgs	260.82	107.00	Rs one hundred Seven only
182	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Second Floor	Kgs	260.82	113.00	Rs one hundred thirteen only.

Signature of the Contractor

Executive Engineer (Project) 12/15

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
183	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	72.90	94.00	Rs ninety four only
184	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	7.56	4877.00	Rs Four thousand Eight hundred Seventy Seven only
185	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	12.42	4883.00	Rs Four thousand Eight hundred Eighty three only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
186	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	12.42	4889.00	Rs Four thousand Eight hundred eighty nine only
187	Providing and laying in positon plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregrates @ 0.69cum and fine aggregates @ 0.43cum,with super plastisiser @ 3 litres confirming to IS 9103-1999 reaffirmed-2008, machine mixed concrete laid in layers not exceeding 15 cms thick will compacted in foundation, plinth and cills including cost of all materials, labour, HOM of machinery curing complete as per specifications.	Cum	5.28	6702.00	Rs Six thousand Seven hundred two only
188	Extra for use of water proofing compound in cement concrete of mix M-20, @ 1kg of compound per Bag of cement.	Cum	5.28	224.00	Rs Two hundred twenty four only.
189	Fixtures Providing and fixing of Door locking arrangements	Each	5.00	709.00	Rs Seven hundred nine only
190	Providing and fixing of Handles powder coated 150mm	Each	10.00	63.00	Rs Sixty three only
191	Providing and fixing of Hinges 5" heavy duty	Each	20.00	41.00	Rs Fourty one only
192	Providing and fixing of Hold fasts MS	Each	5.00	43.00	Rs Fourty three only
193	Providing and fixing of Tower bolt 300mm long	Each	10.00	130.00	Rs one hundred thirty only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
194	TOILET BLOCK WITH STAIRCASE (LADIES) - Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification	Cum	94.17	317.00	Rs Three hundred Seventeen only
195	Filling available excavated earth (excluding rock) insides of foundations upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with a lead upto 50m. And lift upto 1.5m including cost of all labour complete as per specifications.	Cum	53.79	142.00	Rs one hundred fifty two only
196	Transportation of excavated earth by mechanical means including loading and unloading with a lead of 20 kmtr and dispersing the same as directed.	Cum	56.50	128.00	Rs one hundred twenty Eight only
197	Providing and laying in position Plain Cement Concrete of mix 1:3:6 with OPC cement @ 220kgs ,with 40mm and down size graded granite metal coarse aggregates @ 0 .892 cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials,labour, HOM of machinery ,curing complete as per specifications.	Cum	7.18	5754.00	Rs Five thousand Seven hundred fifty four only
198	Providing and constructing granite / trap / basalt Size Stone Masonry in cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of maerials, labour, curing Complete as per specifications.	Cum	13.73	4544.00	Rs Four thousand five hundred fifty four only
199	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	19.22	7208.00	Rs Seven thousand two hundred Eight only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
200	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0 70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintes retaining walls, return walls, wals (any thickness) ncluding attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Ground Floor	Cum	11 38	7208.00	Rs Seven thousand two hundred eight only
201	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0 47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, wals (any thickness) including attached plasters, columns piers, abutments, pillars, posts struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. First Floor	Cum	8.92	7267.00	Rs Seven thousand two hundred Sixty Seven only
202	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0 70cum and fine aggregtes @ 0 47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles retaining walls return walls, wals (any thickness) including attached plasters columns piers, abutments, pillars posts struts, buttresses, string or acing courses parapets coping, bed blocks, anchor blocks plain window cills, fillets etc , including cost of all materials, labour, HOM of machinery, curing, complete as per specifications Second Floor	Cum	9 46	7321.00	Rs Seven thousand three hundred twenty Seven only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
203	Providing and removing centering shuttering strutting, propping etc , and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string [illegible] of all materials, labour complete as per specificaitons.	Sqm	40 23	337·00	Rs Three hundred thirty Seven only.
204	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for [illegible] walls and in 15 cms thick layers and well compated including [illegible] curing,etc with all lead and lifts etc complete(exclusive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25	Cum	36 07	7177·00	Rs Seven thousand one hundred Seventy Seven only
205	Providing and removing Centering, shuttering, strutting, propping etc , for [illegible] pillars piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials labour [illegible] complete as per specification and directions of the Engineer in charge Ground Floor	Sqm	27 00	421·00	Rs Four hundred twenty one only
206	Providing and removing Centering shuttering strutting propping etc , for [illegible] pillars, piers abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour [illegible] complete as per specification and directions of the Engineer in charge First Floor	Sqm	43 50	427·00	Rs Four hundred twenty Seven only.
207	Providing and removing Centering, shuttering, strutting, propping etc , for [illegible] pillars piers abutments post and struts square / rectangular / polygon in plan including cost of materials, labour [illegible] complete as per specification and directions of the Engineer in charge Second Floor	Sqm	43 50	433·00	Rs Four hundred thirty three only
208	Providing and removing centering, shuttering, strutting, propping etc , and removal of form work for flat surface such as roofs landings [illegible] and like thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3 5M from Ground level Ground Floor	Sqm	63 70	362·00	Rs Three hundred Sixty two only
209	Providing and removing centering shuttering strutting propping etc and removal of form work for flat surface such as roofs landings [illegible] and like thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3 5M from Ground level First Floor	Sqm	63 70	368·00	Rs Three hundred Sixty eight only.
210	Providing and removing centering shuttering strutting propping etc and removal of form work for flat surface such as roofs landings [illegible] and like thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level Second Floor	Sqm	63 70	374·00	Rs Three hundred Seventy four only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
211	Providing and removing centering, shuttering, strutting, propping etc , and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth including cost of all materials, labour complete as per specifications Ground Floor	Sqm	26 16 ✓	291 00	Rs Two hundred ninety Seven only
212	Providing and removing centering, shuttering strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth including cost of all materials, labour complete as per specifications First Floor	Sqm	36 80 ✓	303 00	Rs Three hundred three only
213	Providing and removing centering shuttering strutting propping etc , and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth including cost of all materials, labour complete as per specifications Second Floor	Sqm	36 80 ✓	309 00	Rs Three hundred nine only .
214	Providing and removing centering shuttering, strutting propping etc , and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton Ground Floor	Sqm	26 67 ✓	553 00	Rs Five hundred fifty three only
215	Providing and removing centering, shuttering, strutting, propping etc , and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton First Floor	Sqm	26 67 ✓	559 00	Rs Five hundred fifty nine only .
216	Providing and removing centering, shuttering, strutting, propping etc and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton Second Floor	Sqm	26 67 ✓	565 00	Rs Five hundred Sixty five only .
217	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0 345cum, with superplastisser @0 225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials labour, HOM of machinery, finishing, curing, complete as per specifications. Ground Floor	Sqm	5 09 ✓	516 00	Rs Five hundred Sixteen only .

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
218	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs with 12mm and down size graded granite metal coarse aggregates @0.517cum and fine aggregtes @ 0.345cum with superplastisiser @0.22lts machine mixed well compacted for plain chajja of 7.5 cms average thickness upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications First Floor	Sqm	5.09	522.00	Rs Five hundred twenty two only
219	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.517cum and fine aggregtes @ 0.345cum with superplastisiser @0.22lts machine mixed well compacted for plain chajja of 7.5 cms average thickness upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing curing, complete as per specifications. Second Floor	Sqm	5.09	528.00	Rs Five hundred twenty Eight only.
220	Providing and laying in Mat for RCC roof at below the steel for avoiding concrete cement slurry as per the requirement of Engineer incharge	Sqm	211.14	73.00	Rs Seventy three only
221	Providing and removing Centering, shuttering, strutting, propping etc and removal of from work for vertical surfaces such as walls at any thickness including attched plasters, butresses, plinth cills and string courses cost of all materials labour complete as per specification	Sqm	34.32	337.00	Rs Three hundred thirty Seven only
222	Providing and removing centering, shuttering, strutting propping etc for chajjas corbalsetc , including edges including cost of all materials, labour complete as per specifications Ground Floor	Sqm	5.09	312.00	Rs Three hundred twelve only.
223	Providing and removing centering, shuttering, strutting propping etc for chajjas corbalsetc including edges including cost of all materials labour complete as per specifications First Floor	Sqm	5.09	318.00	Rs Three hundred eighteen only.
224	Providing and removing centering, shuttering, strutting propping etc for chajjas,corbalsetc , including edges including cost of all materials labour complete as per specifications Second Floor	Sqm	5.09	324.00	Rs Three hundred twenty four only
225	Providing TMT Steel Reinforcement for RCC work including straightening cutting, bending, hooking, placing in position, lapping and / or welding wherever required tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials labour, HOM of machinery complete as per specifications TMT Bars Fe 500 Ground Floor	MT	4.34	64188.00	Rs Sixty four thousand one hundred Eighty eight only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
226	Providing TMT Steel Reinforcement for R C.C work includ ng straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery comp.ete as per specifications TMT Bars Fe 500 First F oor	MT	2 30	65716.00	Rs Sixty five thousand Seven hundred Sixteen only
227	Provid ng TMT Steel Reinforcement for R C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500 Second Floor	MT	2 48	66244.00	Rs Sixty Six thousand two hundred forty four only.
228	Provid ng and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1.4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications Ground Floor	Sqm	53 28	1119.00	Rs one thousand one hundred nineteen only
229	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete B ocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications First Floor	Sqm	89.50	1155.00	Rs one thousand one hundred fifty five only
230	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of s.ze (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Second Floor	Sqm	89 50	1190.00	Rs one thousand one hundred ninety only
231	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1.4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I S 2185/1965 in Super structure including cost of a l materials, labour charges, scaffolding, curing complete as per spec.f cations Ground Floor	Sqm	28 28	816.00	Rs Eight hundred Sixteen only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
232	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I S 2185/1965 in Super structure including cost of all materials, abour charges, scaffolding curing complete as per specifications First Floor	Sqm	55 14	852 00	Rs Eight hunched fifty two only
233	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications Second Floor	Sqm	55 14	888·00	Rs Eight hundred eighty eight only
234	Providing 12mm thick cement plaster in single coat with cement mortar 1 3, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials labour lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials ,abour, curing complete as per specification	Sqm	126 75	246·00	Rs Two hundred forty Six only
235	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour curing complete as per specifications, direction of the Engineer in charge for Inside Ground Floor	Sqm	116 39	278·00	Rs Two hundred Seventy eight only
236	Providing 18mm thick cement plaster in single coat with cement mortar 1 4, to brick masonry including rounding off corners wherver required smooth rendering · Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications direction of the Engineer in charge for Inside First Floor	Sqm	217 30	284·00	Rs Two hundred eighty four only.
237	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour curing complete as per specifications, direction of the Engineer in charge for Inside Second Floor	Sqm	217 30	290·00	Rs Two hundred ninety only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
238	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering Ground Floor	Sqm	61.98	249.00	Rs Two hundred forty nine only.
239	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering. First Floor	Sqm	106.78	261.00	Rs Two hundred Sixty one only.
240	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, . Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering. Second Floor	Sqm	106.78	273.00	Rs Two hundred Seventy three only.
241	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications size of 30x30cms 6mm thick Ground Floor	Sqm	48.75	1334.00	Rs one thousand three hundred thirty four only
242	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications size of 30x30cms 6mm thick.First Floor	Sqm	48.75	1336.00	Rs one thousand three hundred thirty Six only
243	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick Second Floor	Sqm	48.75	1337.00	Rs one thousand three hundred thirty Seven only

17952

17/1/15

Executive Engineer (Project)

No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
[illegible]	[illegible] Skirting Dado, rises of steps with colour glazed tiles 6mm [illegible] 10mm thick cement plaster 1:3 and jointed with white cement [illegible] over rough plaster surface (excluding cost of rough plastered [illegible] which should be measured and paid separately) using glazed [illegible] of approved make and size including cost of materials labour [illegible] complete as per specifications size 15 x 15 cms [illegible] mm thick Ground Floor	Sqm	71 90	1162·00	Rs one thousand one hundred Sixty two only
244	Providing Skirting, Dado rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials labour. Complete as per specifications. size 15 x 15 cms - 6mm thick First Floor	Sqm	80 54	1164·00	Rs one thousand one hundred Sixty four only
245	Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials labour Complete as per specifications. size 15 x 15 cms - 6mm thick Second Floor	Sqm	80 54	1165·00	Rs one thousand one hundred Sixty five only
247	Flooring with 20mm thick polished shahabad slabs using cement mortar 1 6 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials labour, curing, polishing complete as per specifications Ground Floor	Sqm	75 92	1362·00	Rs one thousand three hundred Sixty two only
248	Flooring with 20mm thick polished shahabad slabs using cement mortar 1 6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab including cost of materials labour curing, polishing complete as per specifications First Floor	Sqm	75 92	1364·00	Rs one thousand three hundred Sixty four only
249	Flooring with 20mm thick polished shahabad slabs using cement mortar 1 6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials labour curing, polishing complete as per specifications Second Floor	Sqm	75 92	1365·00	Rs one thousand three hundred Sixty five only

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
250	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications	Sqm	677 74	64 00	Rs Sixty four only
251	Prov ding and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other fore gn matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per the directions of the Engineer in charge. (with Primer)	Sqm	550 99	101.00	Rs one hundred one only
252	Providing and applying pa nting in two coats with plastic Emulsion pa nt of approved brand on ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the direct ons of the Engineer in charge. (with Primer)	Sqm	126 75	106 00	Rs one hundred Six only
253	Providing ACE paint to external walls of approved colour and shade over prime's coat after brooming & cleaning the surface and applying two coats of ACE paint with cost of all material,labour lead lift with loading unloading etc.complete as per direction of Engineer in charge of work.	Sqm	275 54	202.00	Rs Two hundred two only.
254	Fixing of door frames in an exisying open ng including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1.3.6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications.	Sqm	24 00	1202 00	Rs one thousand two hundred two only
255	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (exclud ng cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.97	121793.00	Rs one Lakh twenty one thousand Seven hundred Ninety three only.

Signature of the Contractor

Executive Engineer (Project) 17/1/17

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
256	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per Specifications. Ground Floor	Sqm	12 58	5368·00	Rs Five thousand three hundred Sixty eight only
257	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per Specifications First Floor	Sqm	13 55	5372·00	Rs Five thousand three hundred Seventy two only
258	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications Second Floor	Sqm	13 55	5376·00	Rs Five thousand three hundred Seventy Six only
259	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications	Sqm	89 25	96·00	Rs Ninety Six only
260	Providing and fixing M S grill work for windows and ventilators weighing 21kg/sqm using M S flats, or M.S. square rods, or combination of M S flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of materials, fixtures, labour and HOM of machinery complete as per specifications Ground Floor	Kgs	139 86	101·00	Rs One hundred one only
261	Providing and fixing M S grill work for windows and ventilators weighing 21kg/sqm using M S flats or M S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures labour and HOM of machinery complete as per specifications First Floor	Kgs	139 86	107·00	Rs one hundred Seven only.
262	Providing and fixing M S.grill work for windows and ventilators weighing 21kg/sqm using M S flats, or M S square rods, or combination of M S flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications Second Floor	Kgs	139 86	113·00	Rs one hundred thirteen only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
263	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	44.96	94.00	Rs Ninety four only
264	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm, weight 0.417 kg./m. shutter sideouter 40mmx18mm, wall thickness 1.25mm, weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	6.66	4877.00	Rs Four thousand eight hundred Seventy Seven only

17/5

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
265	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar.(using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder ofapproved quality.) First Floor	Sqm	6.66	4883.00	Rs Four thousand eight hundred eighty three only
266	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar.(using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder ofapproved quality.) Second Floor	Sqm	6.66	4889.00	Rs Four thousand eight hundred eighty nine only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
267	Providing and laying in positon plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregrates @ 0.69cum and fine aggregates @ 0.43cum,with super plastisiser @ 3 litres confirming to IS 9103-1999 reaffirmed-2008, machine mixed concrete laid in layers not exceeding 15 cms thick will compacted in foundation, plinth and cills including cost of all materials, labour, HOM of machinery curing complete as per specifications.	Cum	5.28	6702.00	Rs Six thousand Seven hundred two only
268	Extra for use of water proofing compound in cement concrete of mix M-20, @ 1kg of compound per Bag of cement.	Cum	5.28	224.00	Rs Two hundred twenty four only
269	Fixtures Providing and fixing of Door locking arrangements	Each	8.00	709.00	Rs Seven hundred nine only
270	Providing and fixing of Handles powder coated 150mm	Each	8.00	63.00	Rs Sixty three only
271	Providing and fixing of Hinges 5" heavy duty	Each	30.00	41.00	Rs Fourty one only
272	Providing and fixing of Hold fasts MS	Each	10.00	43.00	Rs Fourty three only
273	Providing and fixing of Tower bolt 300mm long	Each	16.00	130.00	Rs one hundred thirty only.

Signature of the Contractor

Executive Engineer (Project)